

QUOTATION

IMMERSIVE SCREENS PROGRAMME - MISK

MISK ART WEEK 2026 TUNNEL + IMMERSIVE ROOM

TO:

Client: PLOP Makers

FROM:

Miradore Experiences Company, Riyadh

PROJECT DETAILS:

Project: Immersive screens - tunnel and room

Location: MISK, Riyadh

Event: Misk Art Week 2026, 05 - 10 December 2026

QUOTATION NO:

MRD-QT-2026-1006

QUOTATION DATE:

06 October 2026

Supersedes quotation MRD-QT-2026-0914

SCHEDULE OF SERVICES - OUR FEE

S#	PHASE / DESCRIPTION	AMOUNT, SAR
1	Content development - immersive content around MISK City Creative development and production of the immersive content programme presented around MISK City: concept and art direction, 3D scene build, motion production, rendering and delivery mastered to the tunnel canvas. Does not include re-working the content for the immersive room, which is quoted at item 5 below.	34,000
2	Tunnel build - Misk Art Week 2026 Setting out, steel erection, screen cabinet installation and alignment to the arch geometry, cable and power runs behind the surfaces, mapping, colour calibration, commissioning, site supervision and HSE.	80,000
3	Technical support during Art Week - 6 days at SAR 7,500 per day On-site technical crew for the run of Misk Art Week, 5 - 10 December 2026: daily pre-show checks, show operation, in-run maintenance and spares handling. Based on a ten hour day; additional hours pro rata.	45,000
4	Dismantling of the tunnel Controlled dismantle of the screen cabinets and supporting structure, condition report on each cabinet, packing and handover for transfer to the immersive room build. Priced at 5% of the tunnel build cost.	4,000
5	Content re-master for the immersive room Re-working the Art Week content for the five-surface room canvas: re-scaling to the room resolution, re-stitching across the wall, corner and floor surfaces, re-blending the seams and re-rendering. The tunnel and room canvases differ in geometry and resolution, so the content cannot be transferred as is.	18,000
6	Immersive room build - MISK Re-installation of the same screens as the five-surface immersive room: setting out, steel erection, cabinet install and alignment, arc corner forming, floor build, first and second fix, mapping, colour calibration, commissioning, supervision, HSE and the handover file.	68,000

COST SUMMARY

Services subtotal:	249,000
VAT (15%):	37,350.00
TOTAL PAYABLE (INC. VAT):	286,350.00

Amount in words: Two Hundred and Eighty Six Thousand Three Hundred and Fifty Saudi Riyals Only

INDICATIVE PROGRAMME

Content lock	Mid November 2026
Tunnel build and commissioning	01 - 04 December 2026
Misk Art Week 2026	05 - 10 December 2026
Dismantle and condition report	11 - 13 December 2026
Immersive room build	From mid December 2026, handover January 2027

The same screens serve both builds, so the immersive room cannot commence until the tunnel is dismantled and the cabinets are condition checked. Dates are indicative and will be confirmed against the site survey and the Misk Art Week build access windows.

EQUIPMENT AND MATERIALS - NOT INCLUDED IN THIS QUOTATION

S#	ITEM	DETAIL	SUPPLY
1	Structural steel	Sections, plates, fixings and treatment for both structures	By client / quoted separately
2	Cable, wire and containment	Data and power cable, trays, trunking and connectors	By client / quoted separately
3	Power distribution components	Distribution boards, breakers and surge protection	By client / quoted separately
4	Floor deck and pedestals	Load bearing deck, adjustable feet and top layer	By client / quoted separately
5	Access and lifting equipment	Scaffold, mobile towers, lifting gear and crane time	By client / quoted separately
6	Screens, media and processing	LED cabinets, processors, servers and spare cabinets	By client / quoted separately
7	Storage and transport	Storage between the two builds and transfer between sites	By client / quoted separately
8	Permits and approvals	Event permits, structural certification and public liability cover	By client / quoted separately

How materials are handled. All equipment and materials above are to be arranged and supplied by the client, or quoted by Miradore separately on request. Where Miradore supplies them, they are priced once the survey is signed off and invoiced at cost.

PAYMENT TERMS

80% Advance Payment - 20% On Completion and Handover of each phase

NOTES

- All prices are in Saudi Riyals (SAR).
- This quotation supersedes quotation MRD-QT-2026-0914 in full.
- The same screens serve both builds. The room build follows the dismantle and cannot run concurrently.
- Tunnel length and geometry are limited by the screen inventory, confirmed at survey.
- Pricing assumes the tunnel is sited indoors. Outdoor siting requires weather protection, quoted separately.
- Technical support is charged at SAR 7,500 per day for the six days of Art Week, based on a ten hour day. Additional days are charged at the same daily rate and additional hours pro rata.
- Dismantling is priced at 5% of the tunnel build cost and covers a controlled dismantle and condition report. Cabinets found damaged on condition check are replaced at the client's cost unless caused by Miradore.
- Equipment and materials listed above are not included and will be arranged by the client or quoted separately at the client's request.
- Content produced for the tunnel is mastered to the tunnel canvas only. Re-use on the room canvas requires the re-scaling and re-stitching quoted at item 5 and cannot be transferred as is.
- The client is to provide safe site access, temporary power, secure storage and a clear work area.
- This quotation is valid for 30 days from the date of issue.



ADEEL AHMED - DIRECTOR

Miradore Experiences Company, Riyadh, KSA

